ESTIMATE AT 100% DESIGN WWTF, 10% COLLECTION SYSTEM	UPDATED COSTS (\$2014)	
ESTIMATED PROJECT COSTS (excludes Facility Plan and previous planning/UGA efforts)		
Preliminary/Other		
Land Acquisition	\$1,400,000	Completed
Environmental/Cultural Review	\$276,000	Completed
Permitting	\$60,000	Completed
Other Preliminary (fund, public involvement, etc.) 30%	\$316,000	Completed
Public involvement/information	\$73,000	Ongoing
Other (Value Engineering/LID/Legal)	\$500,000	Ongoing
County Project Administration	\$525,000	Ongoing
Utility Operations Startup	\$220,000	
Subtotal Preliminary	\$3,370,000	
Water Reclamation & Pipeline - Common		
Construction ¹	\$15,496,000	
Design: 30%	\$500,000	Completed
Design: final & bid documents	\$1,785,000	Completed
Project Restart @ 1%	\$155,000	•
Construction Management @ 10%	\$1,550,000	
Subtotal Common	\$19,486,000	
Future Storage and UV3 to complete initial capacity	\$782,000	Year 6
Total Common Facilities (Treatment, Reuse & Pipeline)	\$23,638,000	
Initial Collection System: Core & Rhody		
Construction ²	\$13,818,000	
Land Acquisition for Pump Stations	\$25,000	
Design @ 15%	\$2,073,000	
Construction Management @ 10%	\$1,382,000	
Establish LID (20% of assumed \$8,000,000 LID) ⁴	\$1,600,000	
Subtotal Initial Collection System	\$18,898,000	
Total System w/Initial Collection System	\$42,536,000	
Option: Include Initial Side Sewer Cost ³	\$2,675,000	
Total Project Cost	\$45,211,000	

- 1 Tetra Tech Water Reclamation Facility and Influent Pipeline 100% Cost Estimate 12-30-2013 ENR Adjusted
- 2. Tetra Tech 10% Opinion of Probable Construction Costs Core and Rhody Drive Collection System includes
 - Mainline sewers in right-of-way and pump stations
 - Service laterals in right-of-way.
- 3. Tetra Tech 10% Opinion of Probable Construction Costs Core and Rhody Drive Collection System includes
 - Service Connection on Private Property.
- 4. The LID is assumed to be able to accommodate \$8,000,000 based on 60% of special benefit. The cost to establish an LID includes a required 10% guaranty fund, 6.5% allowance for interim interest & financing, and 3.5% allowance for final bond financing costs (total 20% of LID-financed construction).